



**LIP DETAIL**



**GROOVING DETAIL**



**SECTION THROUGH A - A**

**NOTES:**

1. RAMP LIP SHALL HAVE A 1/2" BEVELED LIP AT GUTTER.
2. ROUGH BROOM FINISH SHALL BE PARALLEL TO ADJACENT GROOVING.
3. WHEN RAMP IS LOCATED IN CENTER OF CURB RETURN, IT SHALL BE GROOVED IN A HERRINGBONE PATTERN WITH 1/4" GROOVES APPROXIMATELY 1 1/2" O.C. GROOVES SHALL BE ALIGNED TO CROSSWALK STRIPES TO DIRECT BLIND PEDESTRIANS INTO APPROPRIATE CROSSWALK.
4. SLOPE SHALL NEVER EXCEED 8.33%. A CONSISTANT SLOPE OF 8.33% ON ALL HANDICAP RAMPS IS DESIRABLE.
5. WHERE A MINOR STREET INTERSECTS A MAJOR STREET, AND THERE IS NO CROSSWALK ON THE MAJOR STREET, WHEELCHAIR RAMPS SHALL BE SHIFTED TOWARDS THE MINOR STREET.